

SZ-180-36M

Warranty

- ◆ 5 years Manufacturer Warranty
- ◆ Warranty on Electrical Performance: 10 years 90% + 25 years 80% of power output

Manufacturing

- ◆ Original cell sorting system ensures the best electric cell match
- ◆ EL-Testing before packing.
- ◆ Comprehensive module power testing.

Performance

- ◆ Higherer module efficiency and compact size. Weakened hot-spot effect, lower module failure rate and increased stability by shingle-tech.
- ◆ Special connection method lowers the internal resistance and ensures better performance than traditional connection with busbar.
- ◆ IP67 rated junction box, reliable cables and standard MC4 connectors improve the stability



Mechanical Data

Standard Test Conditions AM=1.5, E=1000W/m², TC=25°C

Nominal Power	180W
Cell Type	Monocrystalline
Module Efficiency	20.76%
Maximum Power Current (Impp)	8.61A
Maximum Power Voltage (Vmpp)	20.90V
Open-circuit Voltage (Voc)	24.70V
Short-circuit Current (Isc)	9.13A
Maximum System Voltage	500V
Output Tolerance	±3%
Cable	900mm / 4.0mm ²
Connector Type	MC4 / MC4 Compatible
Module Structure	Aluminum Frame / Glass / EVA / Backsheet
Junction box rating	≥IP67
Diode	✓
Working Temperature	-40°C~+80°C

Packaging

Module Dimensions	1230*705*30mm
Module Weight	9.0kg
Package	Single Package
Pieces per Pallet	Free
Gross Weight per Pallet	Free
Pallet Dimensions	Free

SOLMAX NEW ENERGY B.V.

Address: Zonnebaan 23, 3542 EB Utrecht, the Netherlands

Tel: +31-307855708

Email: info@solarfam.nl

